

Bid No. 2015-4

**Columbia County Board of County Commissioners**

SW Mary Ethel/Cardinal/Forest Lawn

Bid Opening 4/28/2015

Company Name	Amount
John C. Hipp	\$151,832.00
C. A. Boone	\$193,000.00
Anderson Columbia	\$173,840.33

**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS**  
**PROJECT NUMBER 2015-04**  
**SW MARY ETHEL LN, SW CARDINAL PL, & SW FOREST LAWN WAY**  
**ROADWAY RESURFACING**

**BID PROPOSAL**

THE UNDERSIGNED hereby propose to furnish all materials, labor, and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:

	ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL
1	Mobilization	LS	1	\$12,500	\$ 12,500
2	Maintenance of Traffic	LS	1	\$12,375	\$ 12,375
3	Asphalt Concrete, Leveling 75 lb/sy	TN	175	\$ 115.00	\$ 20,125
4	Asphalt Concrete, Surface 135 lb/sy	TN	800	\$ 115.00	\$ 92,000
5	Borrow Material	CY	300	\$ 10.00	\$ 3,000
6	Sod, 30" Strip	SY	3,000	\$ 4.00	\$ 12,000
7	Pavement Markings (Painted & Thermoplastic)	LS	1	\$ 14,000	\$ 14,000
8	Asphalt Speed Humps	EA	2	\$ 1,500.00	\$ 3,000
9	Intersection Widening	LS	1	\$24,000	\$ 24,000

<b>TOTAL</b>	<b>\$193,000</b>
--------------	------------------

**PAY ITEM NOTES**

**Item 2 MOT** - Includes all elements required for M.O.T. and includes temporary centerline delineation and stop bars placed at all non working times. This item should also include cost to clip and clean edge of pavement prior to resurfacing as directed by the engineer.

**Item 3, Asphalt Concrete, Leveling 75 lb/sy** – as required to provide level surface as directed by Engineer and shall also include cleaning and tacking existing asphalt at .06 gal/sy.

**Item 5, Borrow Material** – includes cost to deliver and spread suitable material as directed by the engineer.

**Item 7, Painted Pavement Markings** - shall include stop bars at all stop conditions and double yellow centerline striping on SW Forest Lawn Way and SW Mary Ethel (2 coats each). Special markings and stop bar required on SW Forest Lawn Way at the intersection of US 441 **SHALL** be Thermoplastic

**Item 8, Asphalt Concrete, Speed Hump** – see attached detail for dimensions. To be placed on SW Cardinal Place.

**Item 9, Intersection Widening**- Includes cost to widen intersection with 8" stabilized subgrade, 8" limerock base, 1 1/2" of asphalt (structural), and 1 1/4" asphalt (surface) on SW Forest Lawn Way. Also includes cost to extend 18" concrete pipe (round) 8' long and place concrete M.E.S. per FDOT standards.

**ALL ITEMS MAY BE INCREASED, DECREASED, OR OMITTED AS DIRECTED BY THE ENGINEER.**


**ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO BOTH THE REQUIREMENTS OF THE LATEST FDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE LATEST FDOT DESIGN STANDARDS.**

**ALL INCIDENTAL WORK INCLUDED IN THESE ITEMS  
 ALL UNIT PRICE AND TOTAL SPACES MUST BE FILLED IN TO CORRELATE WITH EACH ITEM**

FIRM CA Boone Construction Inc (Seal)

BY James F Boone President

ATTEST Sherry Fort  
 Sherry Fort Secretary



**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS**  
**PROJECT NUMBER 2015-04**  
**SW MARY ETHEL LN, SW CARDINAL PL, & SW FOREST LAWN WAY**  
**ROADWAY RESURFACING**

**BID PROPOSAL**

THE UNDERSIGNED hereby propose to furnish all materials, labor, and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:

	ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL
1	Mobilization	LS	1	\$ 16,407.07	\$ 16,407.07
2	Maintenance of Traffic	LS	1	\$ 18,835.25	\$ 18,835.25
3	Asphalt Concrete, Leveling 75 lb/sy	TN	175	\$ 108.46	\$ 18,980.50
4	Asphalt Concrete, Surface 135 lb/sy	TN	800	\$ 91.45	\$ 73,160.00
5	Borrow Material	CY	300	\$ 16.04	\$ 4,812.00
6	Sod, 30" Strip	SY	3,000	\$ 2.52	\$ 7,560.00
7	Pavement Markings (Painted & Thermoplastic)	LS	1	\$ 14,529.52	\$ 14,529.52
8	Asphalt Speed Humps	EA	2	\$ 2,870.52	\$ 5,741.04
9	Intersection Widening	LS	1	\$ 13,815.05	\$ 13,815.05

<b>TOTAL</b>	<b>\$ 173,840.43</b>
--------------	----------------------

**PAY ITEM NOTES**

**Item 2 MOT** - Includes all elements required for M.O.T. and includes temporary centerline delineation and stop bars placed at all non working times. This item should also include cost to clip and clean edge of pavement prior to resurfacing as directed by the engineer.

**Item 3, Asphalt Concrete, Leveling 75 lb/sy** – as required to provide level surface as directed by Engineer and shall also include cleaning and tacking existing asphalt at .06 gal/sy.

**Item 5, Borrow Material** – includes cost to deliver and spread suitable material as directed by the engineer.

**Item 7, Painted Pavement Markings** - shall include stop bars at all stop conditions and double yellow centerline striping on SW Forest Lawn Way and SW Mary Ethel (2 coats each). Special markings and stop bar required on SW Forest Lawn Way at the intersection of US 441 **SHALL** be Thermoplastic

**Item 8, Asphalt Concrete, Speed Hump** – see attached detail for dimensions. To be placed on SW Cardinal Place.

**Item 9, Intersection Widening**- Includes cost to widen intersection with 8" stabilized subgrade, 8" limerock base, 1 1/2" of asphalt (structural), and 1 1/4" asphalt (surface) on SW Forest Lawn Way. Also includes cost to extend 18" concrete pipe (round) 8' long and place concrete M.E.S. per FDOT standards.

**ALL ITEMS MAY BE INCREASED, DECREASED, OR OMITTED AS DIRECTED BY THE ENGINEER.**

**ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO BOTH THE REQUIREMENTS OF THE LATEST FDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE LATEST FDOT DESIGN STANDARDS.**

**ALL INCIDENTAL WORK INCLUDED IN THESE ITEMS  
 ALL UNIT PRICE AND TOTAL SPACES MUST BE FILLED IN TO CORRELATE WITH EACH ITEM**


FIRM Anderson Columbia Co., Inc

(Seal)

BY

  
 E. Tony Williams, Jr., Vice President

ATTEST

  
 Karyl L. Howell, Witness

