

**Bid No. 2015-G**

**Columbia County Board of County Commissioners**

**Southside Recreation Complex Concrete Handicap Parking and Sidewalks**

**Bid Opening 5/7/2015**

<b>Company Name</b>	<b>Amount</b>
Creative Concrete Design of Columbia County, Inc.	\$14,990.00
Bestway Concrete	\$13,310.00
Live Oak Management Group, LLC	\$24,340.00
Travis Timmons, LLC	\$18,980.00
Advanta Asphalt	\$22,994.34
RWB Construction	\$22,592.00
ACE Construction Solutions, Inc.	\$19,950.00

Please make checks payable to Creative Concrete Design of Columbia County  
**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS**  
**PROJECT NUMBER 2015-G**

**Southside Recreation Complex – Concrete Handicap Parking and Sidewalks**

**THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:**

	Item	Unit	Quantity	Unit Price	Total
1	Clearing and Grubbing	LS	1	\$ .35	\$ 997. <sup>00</sup>
2	Layout, Grading, and Compacting	LS	1	\$ .50	\$ 1080. <sup>00</sup>
3	ADA Handicap Parking Pad 72' x 30'	EA	1	\$ 3.75 <sup>00</sup>	\$ 8100. <sup>00</sup>
4	Concrete Sidewalks 5' wide x 4" thick	LF	350'	\$ 2.75 <sup>00</sup>	\$ 4812. <sup>50</sup>

PROJECT TOTAL \$ 14,990.<sup>00</sup>

NOTES

1. All items may be increased, decreased, or omitted as directed by the Engineer
2. Payment shall be field verified quantities and engineer acceptance.
3. Item 2 includes cost to remove grass and stockpile. County forces will utilize material to final dress and will place grass.
4. Item 3 includes cost to grade and compact. 6" below concrete shall meet 95% max density of AASHTO T-99.
5. Item 4 shall meet all ADA standards. ½" preformed expansion joints shall be placed at existing concrete connections. Sawed joints shall be placed within 24 hours of concrete placement as directed by the engineer. Slab for ADA Parking shall be 6" thick with 8" thicker edge on approach side with one #5 rebar on stands parallel with approach edge.
6. Item 5 includes meeting all ADA standards. ½" expansion joints shall be placed at existing concrete connections. Sawed joints shall be placed within 24 hours of concrete placement as directed by the engineer.
7. All concrete shall include fiber mesh, 3000 PSI, include WWM (6x6x10/10), light broom finished, and edged with a tool (½ radius).

The contract time shall be 30 days from the date of contract execution.  
 Liquidated damages shall be \$300.00 per day. No work is allowed on Saturdays, Sundays, and/or County designated holidays.

All materials and construction shall conform to both the requirements of the latest FDOT Standard Specifications for Road and Bridge Construction and the latest FDOT Design Standards.

ALL INCIDENTAL WORK INCLUDED IN THESE ITEMS  
 ALL UNIT PRICE AND TOTAL SPACES MUST BE FILLED IN TO CORRELATE WITH EACH ITEM

FIRM Creative Concrete Design of Columbia County INC.  
 1258 SW Sisters Welcome Rd, Lake City (Seal) FL 32024

BY Justin Peeler  
 President

ATTEST Lynne Crawford

COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS  
PROJECT NUMBER 2015-G  
Southside Recreation Complex – Concrete Handicap Parking and Sidewalks

**THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:**

	Item	Unit	Quantity	Unit Price	Total
1	Clearing and Grubbing	LS	1		\$ 250 <sup>00</sup>
2	Layout, Grading, and Compacting	LS	1		\$ 250 <sup>00</sup>
3	ADA Handicap Parking Pad 72' x 30'	EA	1	\$ 3.50 <i>sq ft</i>	\$ 7560 <sup>00</sup>
4	Concrete Sidewalks 5' wide x 4" thick	LF	350'	\$ 3.00 <i>sq ft</i>	\$ 5250 <sup>00</sup>

PROJECT TOTAL \$ 13,310<sup>00</sup>

NOTES

1. All items may be increased, decreased, or omitted as directed by the Engineer
2. Payment shall be field verified quantities and engineer acceptance.
3. Item 2 includes cost to remove grass and stockpile. County forces will utilize material to final dress and will place grass.
4. Item 3 includes cost to grade and compact. 6" below concrete shall meet 95% max density of AASHTO T-99.
5. Item 4 shall meet all ADA standards. ½" preformed expansion joints shall be placed at existing concrete connections. Sawed joints shall be placed within 24 hours of concrete placement as directed by the engineer. Slab for ADA Parking shall be 6" thick with 8" thicker edge on approach side with one #5 rebar on stands parallel with approach edge.
6. Item 5 includes meeting all ADA standards. ½" expansion joints shall be placed at existing concrete connections. Sawed joints shall be placed within 24 hours of concrete placement as directed by the engineer.
7. All concrete shall include fiber mesh, 3000 PSI, include WWM (6x6x10/10), light broom finished, and edged with a tool (½ radius).

The contract time shall be 30 days from the date of contract execution.  
Liquidated damages shall be \$300.00 per day. No work is allowed on Saturdays, Sundays, and/or County designated holidays.

All materials and construction shall conform to both the requirements of the latest FDOT Standard Specifications for Road and Bridge Construction and the latest FDOT Design Standards.

ALL INCIDENTAL WORK INCLUDED IN THESE ITEMS  
ALL UNIT PRICE AND TOTAL SPACES MUST BE FILLED IN TO CORRELATE WITH  
EACH ITEM

FIRM Bestway Concrete

(Seal)

BY Scott Reed  
President

ATTEST \_\_\_\_\_

COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS  
PROJECT NUMBER 2015-G  
Southside Recreation Complex – Concrete Handicap Parking and Sidewalks

**THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:**

Item	Unit	Quantity	Unit Price	Total
1 Clearing and Grubbing	LS	1	—————	\$ 2,500. <sup>00</sup>
2 Layout, Grading, and Compacting	LS	1	—————	\$ 1,850. <sup>00</sup>
3 ADA Handicap Parking Pad 72' x 30'	EA	1	—————	\$ 13,290. <sup>00</sup>
4 Concrete Sidewalks 5' wide x 4" thick	LF	350'	\$19.14(LF)	\$6,700. <sup>00</sup>

PROJECT TOTAL \$ 24,340.<sup>00</sup>

**NOTES**

1. All items may be increased, decreased, or omitted as directed by the Engineer
2. Payment shall be field verified quantities and engineer acceptance.
3. Item 2 includes cost to remove grass and stockpile. County forces will utilize material to final dress and will place grass.
4. Item 3 includes cost to grade and compact. 6" below concrete shall meet 95% max density of AASHTO T-99.
5. Item 4 shall meet all ADA standards. ½" preformed expansion joints shall be placed at existing concrete connections. Sawed joints shall be placed within 24 hours of concrete placement as directed by the engineer. Slab for ADA Parking shall be 6" thick with 8" thicker edge on approach side with one #5 rebar on stands parallel with approach edge.
6. Item 5 includes meeting all ADA standards. ½" expansion joints shall be placed at existing concrete connections. Sawed joints shall be placed within 24 hours of concrete placement as directed by the engineer.
7. All concrete shall include fiber mesh, 3000 PSI, include WWM (6x6x10/10), light broom finished, and edged with a tool (½ radius).

The contract time shall be 30 days from the date of contract execution.  
Liquidated damages shall be \$300.00 per day. No work is allowed on Saturdays, Sundays, and/or County designated holidays.

All materials and construction shall conform to both the requirements of the latest FDOT Standard Specifications for Road and Bridge Construction and the latest FDOT Design Standards.

ALL INCIDENTAL WORK INCLUDED IN THESE ITEMS  
ALL UNIT PRICE AND TOTAL SPACES MUST BE FILLED IN TO CORRELATE WITH  
EACH ITEM

FIRM Live Oak Management Group LLC

(Seal)

BY Greg Waters  
President

ATTEST Greg Waters

COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS  
PROJECT NUMBER 2015-G  
Southside Recreation Complex – Concrete Handicap Parking and Sidewalks

**THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:**

	Item	Unit	Quantity	Unit Price	Total
1	Clearing and Grubbing	LS	1	1000.00	1000.00
2	Layout, Grading, and Compacting	LS	1	800.00	800.00
3	ADA Handicap Parking Pad 72' x 30'	EA	1	10880.00	10880.00
4	Concrete Sdewalks 5' wide x 4" thick	LF	350'	18	6300.00

PROJECT TOTAL 18,980.00

NOTES

1. All items may be increased, decreased, or omitted as directed by the Engineer
2. Payment shall be field verified quantities and engineer acceptance.
3. Item 2 includes cost to remove grass and stockpile. County forces will utilize material to final dress and will place grass.
4. Item 3 includes cost to grade and compact. 6" below concrete shall meet 95% max density of AASHTO T-99.
5. Item 4 shall meet all ADA standards. ½" preformed expansion joints shall be placed at existing concrete connections. Sawed joints shall be placed within 24 hours of concrete placement as directed by the engineer. Slab for ADA Parking shall be 6" thick with 8" thicker edge on approach side with one #5 rebar on stands parallel with approach edge.
6. Item 5 includes meeting all ADA standards. ½" expansion joints shall be placed at existing concrete connections. Sawed joints shall be placed within 24 hours of concrete placement as directed by the engineer.
7. All concrete shall include fiber mesh, 3000 PSI, include WWM (6x6x10/10), light broom finished, and edged with a tool (½ radius).

The contract time shall be 30 days from the date of contract execution.  
Liquidated damages shall be \$300.00 per day. No work is allowed on Saturdays, Sundays, and/or County designated holidays.

All materials and construction shall conform to both the requirements of the latest FDOT Standard Specifications for Road and Bridge Construction and the latest FDOT Design Standards.

ALL INCIDENTAL WORK INCLUDED IN THESE ITEMS  
ALL UNIT PRICE AND TOTAL SPACES MUST BE FILLED IN TO CORRELATE WITH  
EACH ITEM

FIRM Travis Timmons LLC \_\_\_\_\_ (Seal)

BY David L. Timmons \_\_\_\_\_  
President

ATTEST [Signature] \_\_\_\_\_

COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS  
PROJECT NUMBER 2015-G  
Southside Recreation Complex – Concrete Handicap Parking and Sidewalks

**THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:**

	Item	Unit	Quantity	Unit Price	Total
1	Clearing and Grubbing	LS	1	\$ 4,140.17	\$ 4,140.17
2	Layout, Grading, and Compacting	LS	1	\$ 3,247.09	\$ 3,247.09
3	ADA Handicap Parking Pad 72' x 30'	EA	1	\$ 10,584.98	\$ 10,584.98
4	Concrete Sidewalks 5' wide x 4" thick	LF	350'	\$ 14.35	\$ 5,022.50

PROJECT TOTAL \$ 22,994.84

NOTES

1. All items may be increased, decreased, or omitted as directed by the Engineer
2. Payment shall be field verified quantities and engineer acceptance.
3. Item 2 includes cost to remove grass and stockpile. County forces will utilize material to final dress and will place grass.
4. Item 3 includes cost to grade and compact. 6" below concrete shall meet 95% max density of AASHTO T-99.
5. Item 4 shall meet all ADA standards. ½" preformed expansion joints shall be placed at existing concrete connections. Sawed joints shall be placed within 24 hours of concrete placement as directed by the engineer. Slab for ADA Parking shall be 6" thick with 8" thicker edge on approach side with one #5 rebar on stands parallel with approach edge.
6. Item 5 includes meeting all ADA standards. ½" expansion joints shall be placed at existing concrete connections. Sawed joints shall be placed within 24 hours of concrete placement as directed by the engineer.
7. All concrete shall include fiber mesh, 3000 PSI, include WWM (6x6x10/10), light broom finished, and edged with a tool (½ radius).

The contract time shall be 30 days from the date of contract execution.  
Liquidated damages shall be \$300.00 per day. No work is allowed on Saturdays, Sundays, and/or County designated holidays.

All materials and construction shall conform to both the requirements of the latest FDOT Standard Specifications for Road and Bridge Construction and the latest FDOT Design Standards.

ALL INCIDENTAL WORK INCLUDED IN THESE ITEMS  
ALL UNIT PRICE AND TOTAL SPACES MUST BE FILLED IN TO CORRELATE WITH  
EACH ITEM

FIRM Advanta Asphalt \_\_\_\_\_ (Seal)

BY [Signature] \_\_\_\_\_  
President

ATTEST [Signature] \_\_\_\_\_

COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS  
PROJECT NUMBER 2015-G  
Southside Recreation Complex – Concrete Handicap Parking and Sidewalks

**THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:**

	Item	Unit	Quantity	Unit Price	Total
1	Clearing and Grubbing	LS	1	1596	1596
2	Layout, Grading, and Compacting	LS	1	2166	2166
3	ADA Handicap Parking Pad 72' x 30'	EA	1	10,565	10,565
4	Concrete Sidewalks 5' wide x 4" thick	LF	350'	23.62	8,265

PROJECT TOTAL 22,592

NOTES

1. All items may be increased, decreased, or omitted as directed by the Engineer
2. Payment shall be field verified quantities and engineer acceptance.
3. Item 2 includes cost to remove grass and stockpile. County forces will utilize material to final dress and will place grass.
4. Item 3 includes cost to grade and compact. 6" below concrete shall meet 95% max density of AASHTO T-99.
5. Item 4 shall meet all ADA standards. 1/2" preformed expansion joints shall be placed at existing concrete connections. Sawed joints shall be placed within 24 hours of concrete placement as directed by the engineer. Slab for ADA Parking shall be 6" thick with 8" thicker edge on approach side with one #5 rebar on stands parallel with approach edge.
6. Item 5 includes meeting all ADA standards. 1/2" expansion joints shall be placed at existing concrete connections. Sawed joints shall be placed within 24 hours of concrete placement as directed by the engineer.
7. All concrete shall include fiber mesh, 3000 PSI, include WWM (6x6x10/10), light broom finished, and edged with a tool (1/2 radius).

The contract time shall be 30 days from the date of contract execution.  
Liquidated damages shall be \$300.00 per day. No work is allowed on Saturdays, Sundays, and/or County designated holidays.

All materials and construction shall conform to both the requirements of the latest FDOT Standard Specifications for Road and Bridge Construction and the latest FDOT Design Standards.

ALL INCIDENTAL WORK INCLUDED IN THESE ITEMS  
ALL UNIT PRICE AND TOTAL SPACES MUST BE FILLED IN TO CORRELATE WITH  
EACH ITEM

FIRM RWB CONSTRUCTION, INC. \_\_\_\_\_ (Seal)

BY Robert Benjamin \_\_\_\_\_  
President

ATTEST Wendy Glover \_\_\_\_\_

