



**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS  
PROJECT NUMBER 2016-01  
County Road 341S – SW Sister’s Welcome Road**

**BID PROPOSAL**

THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:

	ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL
1	Mobilization	LS	1	\$133,350.72	\$133,350.72
2	Maintenance of Traffic	LS	1	\$87,592.16	\$87,592.16
3	Silt Fence	LF	3800	\$1.56	\$5,928.00
4	Milling - +/- 1.5"	SY	45500	\$1.48	\$67,340.00
5	Milling - +/- 4"	SY	27300	\$3.05	\$83,265.00
6	Mixing Existing Pavement, 10" Depth	SY	14900	\$1.10	\$16,390.00
7	Limerock Base (3" loose measure)	CY	1300	\$28.43	\$36,959.00
8	Grading and Finishing Mixed Base	LS	1	\$26,052.05	\$26,052.05
9	Asphaltic Conc. SP 12.5 165 lbs/sy Structural	TN	1250	\$87.77	\$109,712.50
10	Asphaltic Conc. SP 9.5 165 lbs/sy Surface	TN	6010	\$83.70	\$503,037.00
11	Asphaltic Conc. SP 12.5 275 lbs/sy Structural	TN	1700	\$84.99	\$144,483.00
12	Miscellaneous Asphalt Pavement	TN	7	\$721.05	\$5,047.35
13	Resurfacing - Paved County Intersections	TN	300	\$126.31	\$37,893.00
14	Construction - Unpaved County Intersections	SY	360	\$39.85	\$14,274.00
15	Shoulder Rework	LS	1	\$16,780.51	\$16,780.51
16	Borrow	CY	1500	\$18.21	\$27,315.00
17	End Anchorage Assembly - Flared	EA	2	\$2,833.07	\$5,666.14
18	End Anchorage Assembly - Fleet 350	EA	2	\$2,833.07	\$5,666.14
19	Sod - Bermuda	SY	6800	\$2.14	\$14,552.00
20	See and Mulch	LS	1	\$5,540.22	\$5,540.22
21	Painted Pavement Markings	LS	1	\$52,254.38	\$52,254.38
				<b>TOTAL:</b>	<b>\$1,379,098.17</b>

CONTRACTOR INITIAL: 

**PAY ITEM NOTES**

**Item 2** - Shall include all elements required per FDOT standards and include temporary centerline/stop bar delineation at all non working times, stationing/existing profile/offsets, and any edge of pavement reclamation where required.

**Item 3** - Shall be placed at all areas of potential stormwater runoff as directed by the Engineer.

**Item 4 & Item 5** - Contractor to match slopes in curved sections and widened turnlane sections and provide 2% cross slopes in tangent sections of roadway as directed by the Engineer. Contractor shall deliver millings to Columbia County Public Works Site, off CR 25A, at Columbia County Parcel #19-3S-17-05099-000.

**Item 6** - Average depth shall be 10" and shall be achieved with a milling machine or engineer approved equivalent.

**Item 7** - Shall include 3" limerock, loose measure, placed by mechanical spreader before mixing begins.

**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS  
PROJECT NUMBER 2016-01  
County Road 341S – SW Sister's Welcome Road**

**Item 8** - Includes all construction layout required, shaping, compacting, finishing, and priming before placement of asphalt.

**Item 10** - Shall place 165 lb/sy of SP 9.5 asphalt on all existing paved county intersections.

**Item 14**- Shall include 8" compacted subgrade, 6" of limerock base, and 165 lb/sy of SP 9.5 asphalt on all existing non paved county intersections as directed by the engineer.

**Item 15** – Shall include mixing and shaping of shoulders in mixed portion of project to prepare for grassing placement.

**Item 16** – Shall be placed at the direction of the engineer.

**Item 18** – Includes cost to place Fleet 350 type end treatments on guardrail terminations.

**Item 19** – Includes cost to place 42" sod strip along edge of pavement in mixed portion of the project and in areas directed by the engineer.

**Item 20** - Shall be placed at all disturbed areas not sodded, as directed by the engineer.

**Item 21**- Shall include striping the roadway back to existing layout and shall include stop bars at all stop conditions, centerline/edgeline striping (2 coats each), and RPM's throughout.


**ALL ITEMS MAY BE INCREASED, DECREASED, OR OMITTED AS DIRECTED BY THE ENGINEER.**

**ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO BOTH THE REQUIREMENTS OF THE LATEST FDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE LATEST FDOT DESIGN STANDARDS.**

**ALL INCIDENTAL WORK INCLUDED IN THESE ITEMS. ALL UNIT PRICE AND TOTAL SPACES MUST BE FILLED IN TO CORRELATE WITH EACH ITEM**


**Company Name:** Anderson Columbia Co., Inc

**Authorized  
Company  
Representative:**

  
**Printed Name** E. Tony Williams Jr., Vice President

**Signature**


**Attested By:**

  
**Printed Name** Karyl L. Howell

**Signature**

**Total Bid Amount:** \$1,379,098.17

**Date:** 2/19/16



**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS**  
**PROJECT NUMBER 2016-01**  
**County Road 341S – SW Sister's Welcome Road**

**BID PROPOSAL**

THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:

	ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL
1	Mobilization	LS	1	73,000	73,000
2	Maintenance of Traffic	LS	1	151,495	151,495
3	Silt Fence	LF	3800	2.00	7,600
4	Milling - +/- 1.5"	SY	45500	.99	45,045
5	Milling - +/- 4"	SY	27300	1.83	49,959
6	Mixing Existing Pavement, 10" Depth	SY	14900	1.00	14,900
7	Limerock Base (3" loose measure)	CY	1300	20.80	27,040
8	Grading and Finishing Mixed Base	LS	1	10,000	10,000
9	Asphaltic Conc. SP 12.5 165 lbs/sy Structural	TN	1250	93.00	116,250
10	Asphaltic Conc. SP 9.5 165 lbs/sy Surface	TN	6010	93.00	558,930
11	Asphaltic Conc. SP 12.5 275 lbs/sy Structural	TN	1700	93.00	158,100
12	Miscellaneous Asphalt Pavement	TN	7	428.00	3,000
13	Resurfacing - Paved County Intersections	TN	300	120.00	36,000
14	Construction - Unpaved County Intersections	SY	360	43.00	15,480
15	Shoulder Rework	LS	1	6,500	6,500
16	Borrow	CY	1500	10,000	15,000
17	End Anchorage Assembly - Flared	EA	2	3,950	7,900
18	End Anchorage Assembly - Fleet 350	EA	2	3,950	7,900
19	Sod - Bermuda	SY	6800	3.03	20,604
20	See and Mulch	LS	1	9,600	9,600
21	Painted Pavement Markings	LS	1	45,000	45,000
				TOTAL:	1,379,303.00

CONTRACTOR INITIAL: \_\_\_\_\_

**PAY ITEM NOTES**

**Item 2** - Shall include all elements required per FDOT standards and include temporary centerline/stop bar delineation at all non working times, stationing/existing profile/offsets, and any edge of pavement reclamation where required.

**Item 3** - Shall be placed at all areas of potential stormwater runoff as directed by the Engineer.

**Item 4 & Item 5** - Contractor to match slopes in curved sections and widened turnlane sections and provide 2% cross slopes in tangent sections of roadway as directed by the Engineer. Contractor shall deliver millings to Columbia County Public Works Site, off CR 25A, at Columbia County Parcel #19-3S-17-05099-000.

**Item 6** - Average depth shall be 10" and shall be achieved with a milling machine or engineer approved equivalent.

**Item 7** - Shall include 3" limerock, loose measure, placed by mechanical spreader before mixing begins.

**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS  
PROJECT NUMBER 2016-01  
County Road 341S – SW Sister's Welcome Road**

**Item 8** - Includes all construction layout required, shaping, compacting, finishing, and priming before placement of asphalt.

**Item 10** - Shall place 165 lb/sy of SP 9.5 asphalt on all existing paved county intersections.

**Item 14** - Shall include 8" compacted subgrade, 6" of limerock base, and 165 lb/sy of SP 9.5 asphalt on all existing non paved county intersections as directed by the engineer.

**Item 15** - Shall include mixing and shaping of shoulders in mixed portion of project to prepare for grassing placement.

**Item 16** - Shall be placed at the direction of the engineer.

**Item 18** - Includes cost to place Fleet 350 type end treatments on guardrail terminations.

**Item 19** - Includes cost to place 42" sod strip along edge of pavement in mixed portion of the project and in areas directed by the engineer.


**Item 20** - Shall be placed at all disturbed areas not sodded, as directed by the engineer.

**Item 21** - Shall include striping the roadway back to existing layout and shall include stop bars at all stop conditions, centerline/edgeline striping (2 coats each), and RPM's throughout.

**ALL ITEMS MAY BE INCREASED, DECREASED, OR OMITTED AS DIRECTED BY THE ENGINEER.**

**ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO BOTH THE REQUIREMENTS OF THE LATEST FDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE LATEST FDOT DESIGN STANDARDS.**

**ALL INCIDENTAL WORK INCLUDED IN THESE ITEMS. ALL UNIT PRICE AND TOTAL SPACES MUST BE FILLED IN TO CORRELATE WITH EACH ITEM**



Company Name: CA Boone Construction (SEAL)

Authorized Company Representative: James F. Boone  
Printed Name President Signature

Attested By: Sherry Font  
Printed Name Secretary Signature Sherry Font

Total Bid Amount: \$1,379,303.00

Date: February 19, 2016