

Bid No. 2017-3

### Columbia County Board of County Commissioners

SW Callahan Ave.

Bid Opening 10/5/17

Company Name	Amount
Anderson Columbia	\$1,140,954.97
Curt's Construction	\$1,328,223.71

**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS  
COLUMBIA COUNTY PROJECT NUMBER 2017-3  
SW Callahan Avenue – Roadway Construction**


Gentlemen:

The undersigned, as bidder, hereby declares that he has examined the contract documents and informed himself fully in regard to all conditions pertaining to the work to be done; that he has examined the specifications for the work and other contract documents relative thereto; and that he has satisfied himself relative to the work to be performed.

The bidder agrees, if this bid is accepted, to contract with the Columbia County Board of County Commissioners to furnish everything necessary to complete the work covered by this bid and other contract documents for the Columbia County Board of County Commissioners. The Contractor assumes full responsibility for all quantities used in his/her bid. The contractor shall coordinate his construction with all proposed utilities on the site.

<b>SW CALLAHAN AVE</b>					
Pay Item No.	Pay Item Description	Quantity	Units	Unit Price	Total Cost
0101 1	Mobilization	1	LS	\$121,654.39	\$121,654.39
0102 1	Maintenance of Traffic	1	LS	\$64,984.81	\$64,981.81
0104 10 3	Sediment Barrier	3,455	LF	\$2.37	\$8,188.35
0102 3	Commercial Material For Temporary Driveway Maintenance	20	CY	\$38.21	\$764.20
0104 18	Inlet Protection System	11	EA	\$111.87	\$1,230.57
0110 1 1	Clearing & Grubbing	8	AC	\$8,499.28	\$67,994.24
0120 4	Subsoil Excavation	642	CY	\$11.92	\$7,652.64
0120 71	Regular Excavation (3-R Projects Only)	1	LS	\$434,888.54	\$434,888.54
0160 4	Type B Stabilization	1,412	SY	\$7.07	\$9,982.84
0285706	Optional Base, Base Group 06	974	SY	\$13.11	\$12,769.14
0286 1	Turnout Construction	514	SY	\$17.76	\$9,128.64
0327 70 1	Milling Exist Asph Pavt, 1" Avg Depth	1,693	SY	\$3.86	\$6,534.98
0334 1 12	Superpave Asphaltic Conc, Traffic B	1,004	TN	\$116.50	\$116,966.00
0425 1341	Inlets, Curb, Type P-4, <10'	5	EA	\$6,970.08	\$34,850.40
0425 1521	Inlets, DT Bot, Type C, <10'	5	EA	\$4,682.86	\$23,414.30
0430174118	Pipe Culvert, Optional Material, Round, 18" SD	24	LF	\$48.68	\$1,168.32
0430175115	Pipe Culvert, Concrete, Round, 15"S/CD	5	LF	\$206.87	\$1,034.35
0430175118	Pipe Culvert, Concrete, Round, 18"S/CD	480	LF	\$44.75	\$21,480.00
0430175124	Pipe Culvert Concrete, Round, 24"S/CD	778	LF	\$48.48	\$37,717.44
0430982129	Mitered End Section, Concrete, Round, 24" CD	2	EA	\$1,009.98	\$2,019.96
0430984125	Mitered End Section, Optional Round, 18" SD	2	EA	\$757.98	\$1,515.96
0520 1 7	Concrete Curb & Gutter, Type E	103	LF	\$16.31	\$1,679.93
0520 1 10	Concrete Curb & Gutter, Type F	1,337	LF	\$14.84	\$19,841.08
0522 1	Sidewalk Concrete, 4" Thick	1,053	SY	\$31.62	\$33,295.86
0522 2	Sidewalk Concrete, 6" Thick	23	SY	\$37.09	\$853.07

CONTRACTOR SIGNATURE

  
E. Tony Williams, Jr., Vice President



**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS  
COLUMBIA COUNTY PROJECT NUMBER 2017-3  
SW Callahan Avenue – Roadway Construction**

Gentlemen:

The undersigned, as bidder, hereby declares that he has examined the contract documents and informed himself fully in regard to all conditions pertaining to the work to be done; that he has examined the specifications for the work and other contract documents relative thereto; and that he has satisfied himself relative to the work to be performed.

The bidder agrees, if this bid is accepted, to contract with the Columbia County Board of County Commissioners to furnish everything necessary to complete the work covered by this bid and other contract documents for the Columbia County Board of County Commissioners. The Contractor assumes full responsibility for all quantities used in his/her bid. The contractor shall coordinate his construction with all proposed utilities on the site.

**SW CALLAHAN AVE**

Pay Item No.	Pay Item Description	Quantity	Units	Unit Price	Total Cost
0101 1	Mobilization	1	LS	105,430	105,430
0102 1	Maintenance of Traffic	1	LS	68,995	68,995
0104 10 3	Sediment Barrier	3,455	LF	1.35	4,664.25
0102 3	Commercial Material For Temporary Driveway Maintenance	20	CY	30.22	604.40
0104 18	Inlet Protection System	11	EA	204.23	2,246.53
0110 1 1	Clearing & Grubbing	8	AC	10,625	85,000
0120 4	Subsoil Excavation	642	CY	6.53	4,192.26
0120 71	Regular Excavation (3-R Projects Only)	1	LS	595,000	595,000
0160 4	Type B Stabilization	1,412	SY	13.69	19,330.28
0285706	Optional Base, Base Group 06	974	SY	18.95	18,457.30
0286 1	Turnout Construction	514	SY	29.77	15,301.78
0327 70 1	Milling Exist Asph Pavt, 1" Avg Depth	1,693	SY	6.03	10,208.79
0334 1 12	Superpave Asphaltic Conc, Traffic B	1,004	TN	126.43	126,935.72
0425 1341	Inlets, Curb, Type P-4, <10'	5	EA	6,260.35	31,301.75
0425 1521	Inlets, DT Bot, Type C, <10'	5	EA	3,477.88	17,389.40
0430174118	Pipe Culvert, Optional Material, Round, 18" SD	24	LF	50.08	1,201.92
0430175115	Pipe Culvert, Concrete, Round, 15"S/CD	5	LF	54.80	274.00
0430175118	Pipe Culvert, Concrete, Round, 18"S/CD	480	LF	56.39	27,067.20
0430175124	Pipe Culvert Concrete, Round, 24"S/CD	778	LF	72.61	56,490.58
0430982129	Mitered End Section, Concrete, Round, 24" CD	2	EA	1,238.67	2,477.34
0430984125	Mitered End Section, Optional Round, 18" SD	2	EA	904.19	1,808.38
0520 1 7	Concrete Curb & Gutter, Type E	103	LF	17.10	1,761.30
0520 1 10	Concrete Curb & Gutter, Type F	1,337	LF	14.79	19,774.23
0522 1	Sidewalk Concrete, 4" Thick	1,053	SY	30.98	32,621.94
0522 2	Sidewalk Concrete, 6" Thick	23	SY	49.56	1,139.88

CONTRACTOR SIGNATURE Dana Haynes

**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS  
COLUMBIA COUNTY PROJECT NUMBER 2017-3  
SW Callahan Avenue – Roadway Construction**

0527 2	Detectable Warnings	76	SF	45.35	3,446.60
0530 3 4	Riprap, Rubble, F&I, Ditch Lining	13	TN	160.75	2,089.75
0546 71	Rumble Strips	4	PS	488.37	1,953.48
0570 1 1	Performance Turf	23,373	SY	.27	6,310.71
0570 1 2	Performance Turf, Sod	11,007	SY	2.06	22,674.42
0630 2 11	Conduit, Furnish & Install, Open Trench	144	LF	8.64	1,244.16
0630 2 12	Conduit, Furnish & Install, Directional Bore	103	LF	23.88	2,459.64
0632 7 1	Signal Cable (New or Reconstructed Intersection), F&I	1	PI	2,143.40	2,143.40
0635 2 11	Pull & Splice Box, F&I, 13" x 24" Cover Size	4	EA	696.74	2,786.96
0646 1 11	Aluminum Signals Pole, Pedestal	3	EA	1,248.05	3,744.15
0653 1 11	Pedestrian Signal, Furnish & Install LED Countdown, 1 Way	2	AS	696.74	1,393.48
0653 1 12	Pedestrian Signal, Furnish & Install LED Countdown, 2 Ways	1	AS	1,148.21	1,148.21
0660 2106	Loop Assembly, F&I, Type F	3	AS	596.89	1,790.67
0665 1 11	Pedestrian Detector, Furnish & Install, Standard	4	EA	323.41	1,293.64
0700 1 11	Single Post Sign, F&I Ground Mount, Up To 12 SF	7	AS	282.17	1,975.19
0700 1 50	Single Post Sign, Relocate	2	AS	108.53	217.06
0706 3	Retro-Reflective Pavement Markers	160	EA	5.43	868.80
0710 90	Painted Pavement Markings, Final Surface	1	LS	8,899.16	8,899.16
0711 17	Thermoplastic, Remove	380	SF	4.34	1,649.20
9999999990	Pipe Culvert, Optional Material, Round, 10"SD	150	LF	30.42	4,563.00
9999999991	Mitered End Section, Optional Round, 10" SD	10	EA	589.78	5,897.80

GRAND TOTAL 1,328,223.71

CONTRACTOR SIGNATURE Dana Haynes

ADDENDA	
NUMBER	DATE SENT

BID TOTAL FOR SW CALLAHAN AVE. CONSTRUCTION
<u>1,328,223.71</u>