

Bid No. 2018-3

Columbia County Board of County Commissioners

SW King Street and SW Mauldin Ave

Bid Opening 5/3/2018

Company Name	Amount
Anderson Columbia	\$1,187,141.78
C.A. Boone Construction	\$1,193,300.00
Curt's Construction	\$1,314,883.38

COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS
PROJECT NUMBER 2018-03
SW KING STREET AND SW MAULDIN AVENUE – ROADWAY IMPROVEMENTS

BID PROPOSAL

THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:

	ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL
1	Mobilization	LS	1	\$ 58,732.00	\$58,732.00
2	Maintenance of Traffic	LS	1	\$ 48,222.00	\$48,222.00
3	Staked Silt Fence	LF	2,000	\$ 1.55	\$3,100.00
4	Milling, +/- 1.75"	SY	38,500	\$ 1.50	\$57,750.00
5	Limerock	TN	7,155	\$ 11.61	\$83,069.55
6	Subsoil Excavation	CY	827	\$ 19.27	\$15,936.29
7	Borrow Material	CY	653	\$ 14.00	\$9,142.00
8	Grading and Finishing (Roadway & Shoulder)	LS	1	\$147,360.84	\$147,360.84
9	Asphaltic Concrete SP 12.5, 165 lb/sy, Structural	TN	3,500	\$ 88.91	\$311,185.00
10	Asphaltic Concrete SP 9.5, 135 lb/sy, Surface	TN	2,900	\$ 99.07	\$287,303.00
11	Resurfacing County Intersections	TN	175	\$ 238.75	\$41,781.25
12	Pipe Culvert, RCP, Round 18"	LF	104	\$ 65.08	\$6,768.32
13	Mitered End Section, 18"	EA	4	\$ 949.00	\$3,796.00
14	Concrete Box Culvert	LS	1	\$187,117.00	\$187,117.00
15	Sod Strip 42"	SY	13,400	\$ 1.84	\$24,656.00
16	Seed and Mulch	LS	1	\$4,424.13	\$4,424.13
17	Pavement Markings	LS	1	\$24,540.00	\$24,540.00

Contractor Signature : Dana Haynes

TOTAL 1,314,883.38

PAY ITEM NOTES

- Item 2** - Shall include all elements required per FDOT standards and include temporary centerline/stop bar delineation at all non-working times, stationing/offsets with profile of existing centerline elevations, all detour items, and any edge of pavement reclamation.
- Item 3** - Shall be placed at all areas of potential stormwater runoff as directed by the Engineer.
- Item 4** - Average depth is 1 ¾" inches and shall be achieved with a milling machine capable of providing millings with sizes no greater than 2"-3" in size.
- Item 5** - Shall include hauling and spreading to achieve 8" base thickness.
- Item 6** - Shall include cost to remove 24" in depth and replace with suitable fill at 6" compacted lifts.
- Item 7** - Shall be placed and Engineer's direction
- Item 8** - Includes all construction layouts required, scarifying, widening, shaping, compacting, finishing, and priming for placement of asphalt and sod. Roadway shall have a 2% cross slope prior to placement of prime coat.

COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS
PROJECT NUMBER 2018-03
SW KING STREET AND SW MAULDIN AVENUE – ROADWAY IMPROVEMENTS

Item 11 - Includes placement of SP 9.5 @ 135 lb/sy.

Item 12 – Includes placement of 18" RCP 72 LF at CR 240 and two 16 LF RCP extensions at Dyal Avenue. Pipe lengths are inclusive of mitered end pipe sections. Poured concrete portion of mitered end section will be paid for under **Item 13, Mitered End Section, 18", EA.**

Item 14 - Shall include all materials, labor, and equipment needed per FDOT specifications to construct box culvert per engineered drawings including all incidental items.

Item 15 – Includes cost to place 42" sod strip along edge of pavement and in areas directed by the engineer.

Item 16 - Shall be placed at all disturbed areas not sodded, as directed by the engineer.

Item 17 - Shall include striping the roadway back to existing layout and shall include stop bars at all stop conditions, centerline/edgeline striping (2 coats each), and RPM's throughout. *White edgeline paint will be placed 1' off Edge of Pavement, creating 10' travel lanes and 1' paved shoulders.*

ALL ITEMS MAY BE INCREASED, DECREASED, OR OMITTED AS DIRECTED BY THE ENGINEER.

ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO BOTH THE REQUIREMENTS OF THE LATEST FDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE LATEST FDOT DESIGN STANDARDS.

ALL INCIDENTAL WORK INCLUDED IN THESE ITEMS. ALL UNIT PRICE AND TOTAL SPACES MUST BE FILLED IN TO CORRELATE WITH EACH ITEM

Company Name: Curt's Construction, Inc. (SEAL)

Authorized Company Representative: Curtis Haynes *Curtis Haynes*
Printed Name Signature

Attested By: Dana Haynes *Dana Haynes*
Printed Name Signature

Total Bid Amount: 1,314,883.38

Date: 5-3-18

COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS
PROJECT NUMBER 2018-03
SW KING STREET AND SW MAULDIN AVENUE – ROADWAY IMPROVEMENTS

BID PROPOSAL

THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:

	ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL
1	Mobilization	LS	1	\$ 107,717.31	\$ 107,717.31
2	Maintenance of Traffic	LS	1	\$ 46,010.32	\$ 46,010.32
3	Staked Silt Fence	LF	2,000	\$ 1.54	\$ 3,080.00
4	Milling, +/- 1.75"	SY	38,500	\$ 0.95	\$ 36,575.00
5	Limerock	TN	7,155	\$ 16.84	\$ 120,490.20
6	Subsoil Excavation	CY	827	\$ 20.76	\$ 17,168.52
7	Borrow Material	CY	653	\$ 14.99	\$ 9,788.47
8	Grading and Finishing (Roadway & Shoulder)	LS	1	\$ 57,813.18	\$ 57,813.18
9	Asphaltic Concrete SP 12.5, 165 lb/sy, Structural	TN	3,500	\$ 83.53	\$ 292,355.00
10	Asphaltic Concrete SP 9.5, 135 lb/sy, Surface	TN	2,900	\$ 85.05	\$ 246,645.00
11	Resurfacing County Intersections	TN	175	\$ 158.04	\$ 27,657.00
12	Pipe Culvert, RCP, Round 18"	LF	104	\$ 81.21	\$ 8,445.84
13	Mitered End Section, 18"	EA	4	\$ 877.17	\$ 3,508.68
14	Concrete Box Culvert	LS	1	\$ 151,277.60	\$ 151,277.60
15	Sod Strip 42"	SY	13,400	\$ 2.03	\$ 27,202.00
16	Seed and Mulch	LS	1	\$ 7,211.36	\$ 7,211.34
17	Pavement Markings	LS	1	\$ 24,196.30	\$ 24,196.30

Anderson Columbia Co., Inc

Contractor Signature :

E. Tony Williams, Jr., Vice President

TOTAL \$1,187,141.78

PAY ITEM NOTES

- Item 2** - Shall include all elements required per FDOT standards and include temporary centerline/stop bar delineation at all non-working times, stationing/offsets with profile of existing centerline elevations, all detour items, and any edge of pavement reclamation.
- Item 3** - Shall be placed at all areas of potential stormwater runoff as directed by the Engineer.
- Item 4** - Average depth is 1 3/4" inches and shall be achieved with a milling machine capable of providing millings with sizes no greater than 2"-3" in size.
- Item 5** - Shall include hauling and spreading to achieve 8" base thickness.
- Item 6** - Shall include cost to remove 24" in depth and replace with suitable fill at 6" compacted lifts.
- Item 7** - Shall be placed and Engineer's direction
- Item 8** - Includes all construction layouts required, scarifying, widening, shaping, compacting, finishing, and priming for placement of asphalt and sod. Roadway shall have a 2% cross slope prior to placement of prime coat.

**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS
PROJECT NUMBER 2018-03
SW KING STREET AND SW MAULDIN AVENUE – ROADWAY IMPROVEMENTS**

Item 11 - Includes placement of SP 9.5 @ 135 lb/sy.

Item 12 – Includes placement of 18" RCP 72 LF at CR 240 and two 16 LF RCP extensions at Dyal Avenue. Pipe lengths are inclusive of mitered end pipe sections. Poured concrete portion of mitered end section will be paid for under **Item 13, Mitered End Section, 18"**, EA.

Item 14 - Shall include all materials, labor, and equipment needed per FDOT specifications to construct box culvert per engineered drawings including all incidental items.

Item 15 – Includes cost to place 42" sod strip along edge of pavement and in areas directed by the engineer.

Item 16 - Shall be placed at all disturbed areas not sodded, as directed by the engineer.

Item 17 - Shall include striping the roadway back to existing layout and shall include stop bars at all stop conditions, centerline/edgeline striping (2 coats each), and RPM's throughout. *White edgeline paint will be placed 1' off Edge of Pavement, creating 10' travel lanes and 1' paved shoulders.*

ALL ITEMS MAY BE INCREASED, DECREASED, OR OMITTED AS DIRECTED BY THE ENGINEER.

ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO BOTH THE REQUIREMENTS OF THE LATEST FDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE LATEST FDOT DESIGN STANDARDS.

ALL INCIDENTAL WORK INCLUDED IN THESE ITEMS. ALL UNIT PRICE AND TOTAL SPACES MUST BE FILLED IN TO CORRELATE WITH EACH ITEM



Company Name: Anderson Columbia Co., Inc _____ (SEAL)

Authorized Company Representative:  _____
Printed Name E. Tony Williams, Jr., Vice President Signature

Attested By:  _____
Printed Name KARYL Z. HOWELL Signature

Total Bid Amount: \$ 1,187,141.78 _____

Date: May 3, 2018 _____


**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS
PROJECT NUMBER 2018-03
SW KING STREET AND SW MAULDIN AVENUE – ROADWAY IMPROVEMENTS**

BID PROPOSAL

THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:

	ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL
1	Mobilization	LS	1	\$ 53,000.00	\$ 53,000.00
2	Maintenance of Traffic	LS	1	\$ 53,000.00	\$ 53,000.00
3	Staked Silt Fence	LF	2,000	\$ 3.00	\$ 6,000.00
4	Milling, +/- 1.75"	SY	38,500	\$ 1.20	\$ 43,000.00
5	Limerock	TN	7,155	\$ 14.00	\$ 100,170.00
6	Subsoil Excavation	CY	827	\$ 14.00	\$ 11,578.00
7	Borrow Material	CY	653	\$ 8.00	\$ 5,224.00
8	Grading and Finishing (Roadway & Shoulder)	LS	1	\$ 63,000.00	\$ 63,000.00
9	Asphaltic Concrete SP 12.5, 165 lb/sy, Structural	TN	3,500	\$ 96.00	\$ 336,000.00
10	Asphaltic Concrete SP 9.5, 135 lb/sy, Surface	TN	2,900	\$ 96.00	\$ 278,400.00
11	Resurfacing County Intersections	TN	175	\$ 150.00	\$ 26,250.00
12	Pipe Culvert, RCP, Round 18"	LF	104	\$ 33.00	\$ 3,432.00
13	Mitered End Section, 18"	EA	4	\$ 800.00	\$ 3,200.00
14	Concrete Box Culvert	LS	1	\$ 160,000.00	\$ 160,000.00
15	Sod Strip 42"	SY	13,400	\$ 1.80	\$ 24,120.00
16	Seed and Mulch	LS	1	\$ 3,926.00	\$ 3,926.00
17	Pavement Markings	LS	1	\$ 23,000.00	\$ 23,000.00

Contractor Signature :



James F. Boone, President

TOTAL \$1,193,300.00

C.A. Boone Construction, Inc

PAY ITEM NOTES

Item 2 - Shall include all elements required per FDOT standards and include temporary centerline/stop bar delineation at all non-working times, stationing/offsets with profile of existing centerline elevations, all detour items, and any edge of pavement reclamation.

Item 3 - Shall be placed at all areas of potential stormwater runoff as directed by the Engineer.

Item 4 - Average depth is 1 3/4" inches and shall be achieved with a milling machine capable of providing millings with sizes no greater than 2"-3" in size.

Item 5 - Shall include hauling and spreading to achieve 8" base thickness.

Item 6 - Shall include cost to remove 24" in depth and replace with suitable fill at 6" compacted lifts.

Item 7 - Shall be placed and Engineer's direction

Item 8 - Includes all construction layouts required, scarifying, widening, shaping, compacting, finishing, and priming for placement of asphalt and sod. Roadway shall have a 2% cross slope prior to placement of prime coat.

**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS
PROJECT NUMBER 2018-03
SW KING STREET AND SW MAULDIN AVENUE – ROADWAY IMPROVEMENTS**

Item 11 - Includes placement of SP 9.5 @ 135 lb/sy.

Item 12 – Includes placement of 18” RCP 72 LF at CR 240 and two 16 LF RCP extensions at Dyal Avenue. Pipe lengths are inclusive of mitered end pipe sections. Poured concrete portion of mitered end section will be paid for under **Item 13, Mitered End Section, 18”, EA.**

Item 14 - Shall include all materials, labor, and equipment needed per FDOT specifications to construct box culvert per engineered drawings including all incidental items. *Note - "See Attached"

Item 15 – Includes cost to place 42” sod strip along edge of pavement and in areas directed by the engineer.

Item 16 - Shall be placed at all disturbed areas not sodded, as directed by the engineer.

Item 17 - Shall include striping the roadway back to existing layout and shall include stop bars at all stop conditions, centerline/edgeline striping (2 coats each), and RPM's throughout. *White edgeline paint will be placed 1' off Edge of Pavement, creating 10' travel lanes and 1' paved shoulders.*

ALL ITEMS MAY BE INCREASED, DECREASED, OR OMITTED AS DIRECTED BY THE ENGINEER.

ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO BOTH THE REQUIREMENTS OF THE LATEST FDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE LATEST FDOT DESIGN STANDARDS.

ALL INCIDENTAL WORK INCLUDED IN THESE ITEMS. ALL UNIT PRICE AND TOTAL SPACES MUST BE FILLED IN TO CORRELATE WITH EACH ITEM



Company Name: C.A. Boone Construction, Inc

(SEAL)

Authorized Company Representative: James F. Boone, President

Printed Name

Signature

Attested By: Sherry Font, Secretary

Printed Name

Signature

Total Bid Amount: \$1,193,300.00

Date: May 2, 2018