

Columbia County 2019-U
Concrete Bid

Line #	Description	Unit	Qty.	Unit Price	Total Price
1	Mitered End Section, 18" (or equivalent)	EA	75	\$375.00	\$28,125.00
2	Mitered End Section, 24" (or equivalent)	EA	20	\$400.00	\$8,000.00
3	Mitered End Section, 30" (or equivalent)	EA	10	\$400.00	\$4,000.00
4	Mitered End Section, 36" (or equivalent)	EA	10	\$400.00	\$4,000.00
5	Concrete Ditch Pavement (4" Reinforced)	SY	350	\$45.50	\$15,925.00
6	Concrete Ditch Pavement (6" Reinforced)	SY	100	\$55.50	\$5,550.00
7	Sodding Bermuda	SY	500	\$2.75	\$1,375.00
8	Sodding Centipede	SY	500	\$3.20	\$1,600.00
9	Sodding St. Augustine	SY	500	\$4.20	\$2,100.00
10	Sodding Bahia	SY	500	\$2.60	\$1,300.00
11	Seeding and Mulching	SY	4000	\$0.56	\$2,240.00
12	Concrete Curb and Gutter, Type F	LF	100	\$18.50	\$1,850.00
13	Valley Gutter	LF	100	\$12.50	\$1,250.00
14	Concrete Sidewalk (4")	SY	200	\$38.00	\$7,600.00
15	Finish Grading	SY	500	\$6.75	\$3,375.00
16	Restoration Prior to Grassing	SY	500	\$1.50	\$750.00
17	Removal/Disposal of Existing Concrete/Asphalt	SY	100	\$24.00	\$2,400.00
18	Concrete Slab 4" Reinforced	SY	400	\$45.00	\$18,000.00
19	Concrete Slab 6" Reinforced	SY	250	\$54.00	\$13,500.00
20	Concrete Footer	LF	250	\$22.00	\$5,500.00
21	Concrete Column/Pier Footer 3' x 3' x 2'	EA	10	\$350.00	\$3,500.00
22	Concrete Column/Pier Footer 2' x 2' x 2'	EA	10	\$300.00	\$3,000.00
23	Concrete Column/Pier Footer 5' x 5' x 2'	EA	10	\$450.00	\$4,500.00
24	Density Test	EA	1	\$165.00	\$165.00
				Grand Total	\$139,605.00

EA=Each SY=Square Yard LF=Linear Foot SF=Square Foot LS=Lump Sum

Bid Notes:

- Quantities are estimates only and may be increased, decreased or omitted by County
- All items shall include mobilization, maintenance of traffic, and any incidental work needed.
- Payment shall be based on field verified quantities accepted by County
- All concrete shall include fiber mesh, 3000 psi, broom finish, and edged with a tool having 1/2" radius
- Item 1-4 shall be installed per FDOT index 272, attached with this bid.
- Item 11 shall include a mixture of long-term vegetation and quick growing short-term vegetation.
- Item 15 shall include cost to grade and compact 6" below concrete to 95% density per AASHTO T-99
- Item 20, shall include cost to excavate trench 20" wide X 12" deep, place 3 runs of #5 rebar and place/finish concrete to grade.
- Item 21-23, include cost to excavate, place 2 mats of #5 rebar spaced at 6" O/C both directions, and place/finish concrete to grade.
- Item 24 includes the cost to perform a density test per AASHTO T-99. A proctor will need to be included in the cost. Test to be performed by a certified testing company.

Company Name: Creative Concrete Design of Columbia County, Inc.

Signature: 