

# BID TABULATION

Columbia County Board of County Commissioners

Date: December 12, 2023

Project Bid No: 2023-07

Addendums Issued: 2

Company Name Bid Amount

1. Anderson Columbia \$ 2,451,846.93

2. \_\_\_\_\_ \$ \_\_\_\_\_

3. \_\_\_\_\_ \$ \_\_\_\_\_

4. \_\_\_\_\_ \$ \_\_\_\_\_

5. \_\_\_\_\_ \$ \_\_\_\_\_

6. \_\_\_\_\_ \$ \_\_\_\_\_

Witnessed by 

Company Name: Anderson Columbia Co., Inc.

**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS  
COLUMBIA COUNTY PROJECT NUMBER 2023-07  
CR 6 Widening and Resurfacing**

Pay Item No.	Pay Item Description	Quantity	Units	Unit Price	Total Cost
101-1	Mobilization	1	LS	\$219,951.00	\$219,951.00
102-1	Maintenance of Traffic	1	LS	\$124,196.17	\$124,196.17
104-10-3	Sediment Barrier	2000	LF	\$5.22	\$10,440.00
104-11	Floating Turbidity Barrier	236	LF	\$22.05	\$5,203.80
110-1-1	Clearing and Grubbing	5.76	AC	\$8,663.94	\$49,904.29
120-1	Regular Excavation	1125	CY	\$29.22	\$32,872.50
120-4	Subsoil Excavation	400	CY	\$53.93	\$21,572.00
120-6	Embankment	208	CY	\$272.55	\$56,690.40
285 701	Optional Base Group 1	58.9	SY	\$152.24	\$8,966.94
285 701	Optional Base Group 4	263.1	SY	\$40.75	\$10,721.33
285 701	Optional Base Group 9	4243.8	SY	\$25.29	\$107,325.70
286-1	Turnout Construction	1010	SY	\$38.83	\$39,218.30
327-70-1	Milling 1" (Avg Depth)	28797.29	SY	\$3.35	\$96,470.92
327-70-6	Milling 1.5"	4341.53	SY	\$4.29	\$18,625.16
334-1-13	Superpave Asphaltic conc., Traffic Level C	3864	TN	\$155.68	\$601,547.52
337-7-83	Friction Course, Traffic Level C	358.18	TN	\$163.99	\$58,737.94
339-1	Misc Asphalt	77	TN	\$280.29	\$21,582.33
350-5	Cleaning and Sealing Joints	24.32	LF	\$245.05	\$5,959.62
401-70-7T	Restore Spalled areas (Shot Crete TSP)	528	CF	\$430.88	\$227,504.64
430-174-118	Pipe Culvert Optional Material 18", Round	68	LF	\$148.94	\$10,127.92
430-174-124	Pipe Culvert Optional Material 24", Round	320	LF	\$130.14	\$41,644.80
430-175-124	Pipe Culvert Optional Material 24", Round CD	58	LF	\$143.60	\$8,328.80
430-175-136	Pipe Culvert Optional Material 36", Round CD	50	LF	\$252.13	\$12,606.50
430-984-125	Mitered End Section, Optional, Round 18"	4	EA	\$1,894.81	\$7,579.24
430-984-129	Mitered End Section, Optional, Round 24"	16	EA	\$2,185.40	\$34,966.40
430-982-638	Mitered End Section, Optional, Round 36" CD	2	EA	\$5,911.92	\$11,823.84
430-982-629	Mitered End Section Optional, Round 24", CD	2	EA	\$2,876.89	\$5,753.78
460-71-1	Metal Traffic Railing	731	LF	\$306.32	\$223,919.92
524-2-1	Concrete Slope Pavement	31	SY	\$367.58	\$11,394.98
536-1-1	Guardrail (TL-3)	1238	LF	\$34.31	\$42,475.78
536-7-2	Special Guardrail Post	78	EA	\$306.32	\$23,892.96
536-8-122	Guardrail Transition Connection	4	AS	\$4,533.47	\$18,133.88
536-85-24	End Treatment	8	AS	\$4,288.42	\$34,307.36
538-1	Guardrail Reset	100	LF	\$18.38	\$1,838.00
546-71-1	Raised Rumble Strips, per set	4	EA	\$1,470.32	\$5,881.28
546-72-3	Ground-In Rumble Strips, Sinusoidal	8.877	GM	\$2,175.58	\$19,312.62
570-1-1	Performance Turf	1536	SY	\$2.14	\$3,287.04
570-1-2	Performance Turf, Sod	10082	SY	\$3.98	\$40,126.36
570-1-3	Performance Turf Treatment 2	11298	SY	\$3.98	\$44,966.04
700-1-11	Single Post Sign	9	EA	\$545.24	\$4,907.16
700-1-60	Single Post Sign/Remove	4	EA	\$42.89	\$171.56
705-10-1	Object Marker Type 1	3	EA	\$226.67	\$680.01
705-10-2	Object Marker Type 2	17	EA	\$91.89	\$1,562.13
705-10-3	Object Marker Type 3	3	EA	\$226.67	\$680.01
706-3	Retro-Reflective Pavement Markers	430	EA	\$5.19	\$2,231.70
710-90	Painted Pavement Markings, Final Surface	1	LS	\$55,010.47	\$55,010.47
711-11-124	Thermoplastic Pavement Marking 18" White	219	LF	\$8.82	\$1,931.58
711-11-125	Thermoplastic Pavement Marking Solid 24" White	52	LF	\$14.70	\$764.40
711-15-101	Thermoplastic Pavement Markings Solid 6" White	5.493	GM	\$8,523.17	\$46,817.77
711-15-201	Thermoplastic Pavement Markings Solid 6" Yellow	1.194	GM	\$8,499.25	\$10,148.10
711-15-231	Thermoplastic Pavement Markings Skip 6"	2.19	GM	\$3,234.69	\$7,083.97
<b>ESTIMATED CONSTRUCTION COST</b>					\$2,451,846.93