

BID TABULATION

Columbia County Board of County Commissioners

Date: July 22, 2024

Project Bid No: 2024-08

Addendums Issued: 0

<u>Company Name</u>	<u>Bid Amount</u>
1. <u>Florida Fill & Grading</u>	<u>\$884,870.00</u>
2. <u>Anderson Columbia Co.</u>	<u>\$813,132.62</u>
3. <u>John C. Hipp Construction</u>	<u>\$819,652.20</u>
4. <u></u>	<u>\$</u>
5. <u></u>	<u>\$</u>
6. <u></u>	<u>\$</u>

Witnessed by LaShanda Taylor

819965.2

COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS

PROJECT NUMBER 2024-08

SW Dairy Str

BID PROPOSAL

THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:

ITEM	UNIT	QUANTITY	UNIT COST	TOTAL	
1	Mobilization	LS	1	42,500.00	42,500.00
2	Maintenance of Traffic	LS	1	20,000.00	20,000.00
3	Borrow	CY	200	10.00	2,000.00
4	Milling (±2")	SY	21000	4.00	84,000.00
5	Levelling/Reworking/Finishing milled surface	SY	21000	1.50	31,500.00
6	Asphaltic Conc. SP 9.5 - Surface	TN	1440	198.00	285,120.00
7	Asphaltic Conc. SP 12.5 - Structural	TN	1725	198.00	341,550.00
8	Seed and Mulch	LS	1	3,500.00	3,500.00
9	Sod - 42"	SY	7300	4.00	29,200.00
10	Painted Pavement Markings	LS	1	45,500.00	45,500.00

TOTAL: \$ 884,870.00

Florida Fill + Grading, Inc.

Contractor Name (PRINT):

Jeanette Boone

Contact Signature:

Jeanette Boone, Pres.

MOT

Shall include all elements required per FDOT standards and include temporary centerline/stop bar delineation at all non working times, stationing/offsets, and any edge of pavement reclamation where required.

Silt Fence

Shall be placed at all areas of potential stormwater runoff as directed by the Engineer.

Milling Existing Pavement

Average depth shall be 2" and shall be achieved with a milling machine or engineer approved equivalent. Millings shall be delivered to Public Works Material Yard. Please see attached map.

Level/Rework/Finish Milled Base

After surface is milled, County will inspect limerock base to decide if base requires reworking levelling, finishing, and/or thickening.

Asphalt 9.5 (Surface)

Surface course shall include placement of S.P 9.5 @ 137.5 lbs/SY. To maintain level access to driveways, an apron shall be required at all driveway locations unless other directed by engineer and will be paid for under this item.

Asphalt 12.5 (Structural)

Includes placement of SP 12.5 @ +/-165 lb/sy.

Seed and Mulch

Shall be placed at all disturbed areas not sodded, as directed by the Engineer.

Sod

Includes cost to place sod in areas directed by the Engineer.

**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS
PROJECT NUMBER 2024-08**

SW Dairy Str

BID PROPOSAL

THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:

	ITEM	UNIT	QUANTITY	UNIT COST	TOTAL
1	Mobilization	LS	1	\$67,962.20	\$67,962.20
2	Maintenance of Traffic	LS	1	\$42,676.10	\$42,676.10
3	Borrow	CY	200	\$47.29	\$9,458.00
4	Milling (±2")	SY	21000	\$3.31	\$69,510.00
5	Levelling/Reworking/Finishing milled surface	SY	21000	\$0.51	\$10,710.00
6	Asphaltic Conc. SP 9.5 - Surface	TN	1440	\$170.41	\$245,390.40
7	Asphaltic Conc. SP 12.5 - Structural	TN	1725	\$161.77	\$279,053.25
8	Seed and Mulch	LS	1	\$6,829.38	\$6,829.38
9	Sod - 42"	SY	7300	\$3.79	\$27,667.00
10	Painted Pavement Markings	LS	1	\$53,876.29	\$53,876.29

TOTAL:	\$813,132.62
---------------	---------------------

Contractor Name (PRINT): Anderson Columbia Co., Inc.

Contractor Signature: 
E. Tony Williams Jr., Vice President

MOT Shall include all elements required per FDOT standards and include temporary centerline/stop bar delineation at all non working times, stationing/offsets, and any edge of pavement reclamation where required.

Silt Fence Shall be placed at all areas of potential stormwater runoff as directed by the Engineer.

Milling Existing Pavement Average depth shall be 2" and shall be achieved with a milling machine or engineer approved equivalent. Millings shall be delivered to Public Works Material Yard. Please see attached map.

Level/Rework/Finish Milled Base After surface is milled, County will inspect limerock base to decide if base requires reworking levelling, finishing, and/or thickening.

Asphalt 9.5 (Surface) Surface course shall include placement of S.P 9.5 @ 137.5 lbs/SY. To maintain level access to driveways, an apron shall be required at all driveway locations unless other directed by engineer and will be paid for under this item.

Asphalt 12.5 (Structural) Includes placement of SP 12.5 @ +/-165 lb/sy.

Seed and Mulch Shall be placed at all disturbed areas not sodded, as directed by the Engineer.

Sod Includes cost to place sod in areas directed by the Engineer.

COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS

PROJECT NUMBER 2024-08

SW Dairy Str

BID PROPOSAL

THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:

	ITEM	UNIT	QUANTITY	UNIT COST	TOTAL
1	Mobilization	LS	1	68,810. ⁰⁰	68,810. ⁰⁰
2	Maintenance of Traffic	LS	1	65,234. ⁰⁰	65,234. ⁰⁰
3	Borrow	CY	200	15. ⁰⁰	3,000. ⁰⁰
4	Milling (±2")	SY	21000	2.83	59,430. ⁰⁰
5	Levelling/Reworking/Finishing milled surface	SY	21000	.60	12,600. ⁰⁰
6	Asphaltic Conc. SP 9.5 - Surface	TN	1440	181.48	261,331. ²⁰
7	Asphaltic Conc. SP 12.5 - Structural	TN	1725	176.40	304,290. ⁰⁰
8	Seed and Mulch	LS	1	3000. ⁰⁰	3,000. ⁰⁰
9	Sod - 42"	SY	7300	2.40	17,520. ⁰⁰
10	Painted Pavement Markings	LS	1	24,750. ⁰⁰	24,750. ⁰⁰

TOTAL: \$ 819,652.20

Contractor Name (PRINT): John C Hipp Construction Equip Co.

Contractor Signature: 

MOT

Shall include all elements required per FDOT standards and include temporary centerline/stop bar delineation at all non working times, stationing/offsets, and any edge of pavement reclamation where required.

Silt Fence

Shall be placed at all areas of potential stormwater runoff as directed by the Engineer.

Milling Existing Pavement

Average depth shall be 2" and shall be achieved with a milling machine or engineer approved equivalent. Millings shall be delivered to Public Works Material Yard. Please see attached map.

Level/Rework/Finish Milled Base

After surface is milled, County will inspect limerock base to decide if base requires reworking levelling, finishing, and/or thickening.

Asphalt 9.5 (Surface)

Surface course shall include placement of S.P 9.5 @ 137.5 lbs/SY. To maintain level access to driveways, an apron shall be required at all driveway locations unless other directed by engineer and will be paid for under this item.

Asphalt 12.5 (Structural)

Includes placement of SP 12.5 @ +/-165 lb/sy.

Seed and Mulch

Shall be placed at all disturbed areas not sodded, as directed by the Engineer.

Sod

Includes cost to place sod in areas directed by the Engineer.